# Concrete and its use on the funicular

## Description



The right hand "I" beam, looking uphill, just above Pier 51 (bottom left) showing the calcite bleed and crack running along the flange (arrow). The left hand arrow is just to the right of the insitu joint.

Following on from my post about the metal brackets being use to hold the funicular together <u>(see here)</u> this post takes a further look at WHY the concrete "I" beams have been disintegrating. It is now five weeks since my walk up the funicular and discussions with staff who told me the funicular would be re-opening in five weeks time and the passing loop is still surrounded with scaffolding.

## A crack in the concrete

The ADAC Structures report dated 15/07/2017, obtained by an FOI Request, reported:

"2.2 A crack was clearly seen running along the length of the beam positioned at about mid height of the top flange. It appeared to extend from the lower end up to about mid span. See appendix B for a sketch and photo showing this.

2.3 Some comment on observations:

- The writer has been carrying out annual inspections for the last three years. This feature was observed for the first time during last year's inspection.
- The crack is evident on both sides of the beam at the same height and over the same length.
- The crack is particularly evident due to calcite bleed, showing up white. This was seen as significant at the low end, diminishing along the length."

This crack was *"observed for the first time"* in the 2016 inspection when it was described as being a few cms. long. By the 2017 inspection it had increased to almost 9m! That is more than a crack, it is the top layer of concrete above the reinforcing rebars inside the beam delaminating. Was this caused by water ingress and rusting of the rebar at the insitu joint?

When water gets into a crack and then freezes it will cause damage at that point. The subsequent freeze thaw process, which in a mountain environment could happen several times a day, will gradually weaken and destroy the concrete joint. Eventually the water will work its way through a joint and when reaching the steel rebar will cause corrosion and then potentially delamination along the length of the rebar. Vibration caused by the train will exacerbate the situation.

That this may be the case is shown by the extensive repairs that have taken place on the insitu joint above Pier 51:



Pier 51 viewed from the north side, looking downhill, showing the new rectangular section of



concrete at the insitu joint. Note the absence of scaffolding. September 2023.

Pier 51 view from the south side October 2024. (1) shows the location of the calcite bleed and crack, (2) the extended insitu joint, (3) metal brackets hanging loose on the beam and (4) metal brackets lying on the ground:

## Cause of the crack

The ADAC Structures report explains the crack as follows:-

"5.2 It is thought that the problem is a latent defect within the original fabrication of the beams, most likely due to a cold joint within the concrete pour".

That is one possibility but these "I" beams were manufactured in a factory where conditions and work practices should have been strictly controlled. During and after manufacture there would have been several inspections of the "I" beams:-

- (1) Testing of concrete at the factory to make certain of its suitability,
- (2) Inspection of the "I" beams after being removed from the mould,
- (3) Inspection of the "I" beams when they arrived at Cairn Gorm, and,
- (4) Any problem should have been noted when the beam was being fitted on the piers.

For ADAC to be right FOUR opportunities to identify a problem in any of the "I" beams would have had to have been missed. There is a more likely explanation.

The COWI report of December 2018, also obtained through FOI, stated:

### 3.2 Construction sequence

The sequence of construction shown in construction photographs shows that the precast beams were installed as simply supported spans before the insitu concrete at piers was cast. Therefore under dead loads there would initially be sagging moments but no hogging moments. This could change in time due to concrete creep and differential settlement.

When COWI states that the Type 1 "I" beams *"were installed as simply supported spans"* this means that initially their entire weight was held by the piers on either side and, in the case of the funicular by a small metal plate.



The plate supporting the end of the beams

By contrast to a simply supported span, if the beams in a structure are joined together AND tensioned they then create a "continuous beam" whose weight would be distributed over the entire structure. This difference becomes important when a dead weight – such as a full funicular carriage –exerts force on one beam. If the beam is only simply supported rather than forming part of a continuous structure the

risk of "sagging moments", which cause the beam to crack, increases,

The picture below shows the rebar protruding from the concrete. The lengths of rebar protruding from the top flange were used to connect one "I" beam to the next and hold them in place:



Figure 3-1 Precast beam installation from Cowi Report showing protruding rebars

There are a number of ways to join those top three lengths of rebar to the rebar in the next beam, the most common being:-

(a) tying or lapping them together. Lapped joints are usually held in place using T8 rebar so that there is a gap between the two lengths being joined. This allows the concrete in a pour to fill the gap between them.

(b) using mechanical couplers "Lapped joints are not always an appropriate means of connecting rebar. The use of Ancon Reinforcing Bar Couplers can simplify the design and construction of reinforced concrete and reduce the amount of reinforcement required". (Quote from Ancon)

(c) Welding. This is a challenging way of joining overlapping lengths for a number of reasons:-

(i) The heat produced by welding alters the tensile strength of the rebar, and,

(ii) There is a possibility that when the concrete is poured around those bars that an air gap exists under the bars i.e. the concrete is not in full contact with the rebar thereby decreasing the strength of the join.

Even after a beam is connected to the next one using an insitu joint, in civil engineering terms it

remains a simply supported beam if its entire weight sits on the piers at either end and ONLY becomes part of a <u>continuous beam</u> if couplers are used, effectively post tensioning the structure. While lapping and welding therefore holds supported spans in place, only the use of the correct Ancon, or similar, coupling strengthens the joints and put them under tension changing the beams from simply supported to continuous lengths.

The initial cracking of the beam at Pier 51 could therefore have been caused by sagging of the beam under the train's weight because it was not properly tensioned and that would explain all the stainless steel brackets.

## How were the funicular beams joined?

The insitu joint during construction showing the rebars and how the bottom ends of the "I" beams rests on a small metal plate. Photo credit Cowi Report 2018

Unfortunately, as explained in the COWI report, many of the original plans were lost and it is unclear if the funicular was intended to be one continuous structure.

It does seem, however, from the "Condition report into concrete support structures for Funicular Railway" (November 2015) .that ancon couplers were used around the passing loop:

"4.1 The writer inspected the items listed in the schedule at item 3.1 of this report. It was reported that the installation had been completed in 2001, making it 14 years old. The general condition was thought to be poor for a structure of this age with wide spread minor deficiencies giving a general impression of possible poor quality control during the construction phase".

"4.5.3 Description: This item, in certain locations, gives the greatest cause for concern. The construction drawings made available for the insitu area are stamped "preliminary" and as such no firm conclusions can be based on them. However they show a system for mechanical coupling of the reinforcing bars to provide continuity at some locations. One of these couplers is specified as an Ancon **PB32,** which involves an onsite grouting operation, this would be susceptible to poor quality control. For operational reasons close quarters examination of this joint as a train passes was limited to one location, pier 56. Here the crack was clearly seen opening then closing again, by an estimated 1mm, as the train passed. The concern here is that the coupler may have failed leading to a redistribution of stress to the midspan of the beams that they were not designed to carry. Ref photos [9], [10], [11].

Location: Opening of the joint line between the precast beams and insitu fill. This was wide spread although not universal."

[ N.B. My underline and colour change].

Note the importantce of the couplers: "The concern here is that the coupler may have failed leading to a redistribution of stress to the midspan of the beams that they were not designed to carry".

I have, however, spoken to the welder employed on the original build and he has claimed that Type 1 beams were **welded** together in which case they would remain as "simply supported". How many is not clear.

If the "I" beams remain "simply supported" the industry standards, as advised to me by both a lecturer at a rail engineering college and a civil engineer, would be for the beams to be 10cm deep for every 1m length, i.e. they shey shold be 1.6 to 1.8m deep, depending on the length of a beam, NOT the current 0.8m! In other words, where the protruding rebars have been welded together, rather than being properly coupled and tensioned, or the coupling has failed due to poor quality control, the likelihood of the beams failing will have increased significantly.

# Conclusion.

John Carson, a civil engineer who has been in contract with parkswatch, has today had an interview published with the P & J (see here) and is adamant that concrete should never have been used in the funicular construction. His opinion is that the civil engineers would not request a change in materials and that the whole structure is inherently unsafe because it wasn't built properly. Para 4.1 of the ADAC Structures report, written when the funicular was 14 years old, appears to confirm this observation: *"The general condition was thought to be poor for a structure of this age"*. It is now 23 years old, another 9 years of deterioration!

Can HIE, CM(S)L and others afford to ignore Mr Carson and other civil engineers who now appear prepared to speak out? Given the safety implications that could be classed as reckless at the very least. Will HIE, CM(S)L, DfT and others now take notice and order a full investigation into the funicular before the track collapses and the consequences of that happening?

The major question that still needs to be answered is IF THE ORIGINAL DESIGN WAS FOR A STEEL STRUCTURE, WHO ORDERED OR REQUESTED THE CHANGE FROM STEEL TO CONCRETE WHICH HAS COST THE TAXPAYER £ MILLIONS AND CAUSED CONCERNS OVER PUBLIC SAFETY?

There are still people around who could help answer this. For example, at the time Morrison's tendered for and built the funicular they had a chief civil engineer Michael Martin OBE, who was involved in the construction of the Kessock bridge and then with Morrison's on the construction of the Dornoch Firth and Kylesku bridges, two very successful projects, but there is no mention in his Wikipedia entry of any involvement in the Cairn Gorm funicular! This gentleman transferred to Anglian Water Group (AWG) when they purchased Morrison Construction in 2000, a year before the funicular build was finished, and subsequently worked for Galliford Try, who purchased Morrison Construction from AWG in 2005.

### Category

1. Cairngorms

### Tags

- 1. Cairn Gorm
- 2. funicular
- 3. HIE

Date Created November 11, 2024 Author graham-garfoot